

Merrill W. Carlson
 Chairman

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

4-276

For corners in

Alger
 (County)

Located In:

Corner Code #

1. Public Land Survey

T 49N R 13W J1

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
 in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
 Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

**SURVEY &
 REMONUMENTATION**
 MAY 10 1995
 COMMISSION

FILED
 TIME 9:00 a.m.

APR 20 1995

DONALD W. KINNUNEN
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. Jaaros, in a field survey on October 21, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J1: PLS-John Burt, DS, 1841, Set Qr. Section Post- Y.Pine 14", N.68 E., 54 links, Y.Pine 10", N.50 W., 14 links. CCI Forestry Division, Land and Timber Examination Report, T.J. McLaren, 1949, indicates down GLO Y.Pine BT. Found no other subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J1: Began at BT corner of Sections 1 and 2, T.49N., R.13W. Ran corrected compass line on a GLO bearing West following old blaze line. At 37.73 chains and 6 ft. N. of line found dead and down 24" Pine with notches and a blaze according to GLO survey instructions. Glo notes line tree at 37.52 chains, W.Pine 20". At 40.0 chains there was no monument evident, set temp. point and continued West on corrected compass line following old blaze line. At 80.4 chains measured falling at section corner monument, 4 ft. N. Corrected temp. 1/4 corner position to 40.2 chains and 6 ft. N. of line. Established GLO BT locations NW and NE. Found remains of root system of Y.Pine BT at N.50 W., 14 links. Established corner position from Y.Pine remains and down 24" Pine line tree. W.Pine 9' at N.66 E., (M), 3.18 ft. has "1/4" painted on trunk, faded. Area badly burnt and many downed trees are just charred remains.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J1: Set 2 1/4" Alum. Monument w/ 3 1/4" Alum. Cap stamped to identify corner position. Established reference trees w/ BT signs, blazed, scribed & painted. Set PK nails for measure w/ brass I.D. washers in the following reference trees. R.Pine 20", N.30 W., 24.08 feet, "1/4s BT", R.Pine 8", S.59 W., 41.83 feet, "1/4s BT", R.Pine 8", S.35 1/2 E., 48.87 feet, "1/4s BT", W.Pine 9", N.66 E., 3.18 feet, "1/4s BT", Steel witness post with Survey marker sign, N.09W., 2.0 feet, All bearings are magnetic.

Signed by Robert L. Jaaros
 Surveyor's Michigan License No. 25849

Date 12 April, 1995