

DEC 27 1999

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12-8-1999

Donald W. Kinnunen
Chairman

05-147

For corners in SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

ALGER (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 13W	J9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Section	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED
TIME 1:30 pm
DEC 15 1999
DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. Jamros, in a field survey on August 26, 1999, 19_____, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J9: PLS * Francis Colman, DS, 1851. * Top of Bank, 40 feet, C N-S, and set quarter section post. * Spruce 12", N.41 E., 41 links. * W.Pine 36", S.55 W., 42 links. ***** Michigan Department of Conservation, Forestry Division. * Billy D. Buckler, RLS, 1958. * Replaced corner from 1 W.Pine stump, probable BT. Found old face notch and overgrowth. Stump has burned. Found several other faces on stump. Position fits stream to East and West. Corner lines on top of bank and 1 chain West of Sucker River. * Set 1" pipe with 4" brass cap. * 20" W.Pine stub (1/4s NBT), N.58 E., 90 links. * Re-marked original BT, 36" W.Pine stump (1/4s NBT), S.55 W., 42 links. * Recorded in Liber 2, Page 84, Alger County Corner Records. ***** No other subsequent restoration of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J9: Located corner position by standard field survey methods and found no evidence of monument set in corner report of 1958. Established corner position at mid point and on line between section corners East and West. A search for the W.Pine 36", S.55 W., 42 links (GLO) revealed scattered, burnt remains of a W.Pine stump. No marks of GLO found. * MDCFD NBT at N.58 E., 90 links, 20' W.Pine was found as scattered remains, positive location in question. Set monument at established position and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J9: Set 2 1/2"x30" Berntsen aluminum monument No. A1NB30 with 3 1/4" aluminum cap stamped to identify corner position. * Established the following reference trees with BT signs, blazed, scribed and painted. * Set PK nails for measure with aluminum I.D. washers in the following: W.Pine 5", N.32 E., 14.26 feet, '1/4s BT'. * Spruce 12", S.79 E., 13.58 feet, '1/4s BT'. * W.Pine 6", S.22 W., 8.91 feet, '1/4s BT'. * W.Pine 4", N.37 W., 34.86 feet, '1/4s BT'. * Survey marker sign on 6 foot steel post, S.35 E., 1.2 feet. * All bearings ar magnetic.

Signed by *Robert L. Jamros*
Surveyor's Michigan License No. 25849

Date Dec 13, 1999

