

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 4-8-1995

Donald W. Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-277

For corners in

Alger (County)	Located In:	Corner Code <u>44</u>
1. Public Land Survey	T <u>49N</u> R <u>13W</u>	<u>K1</u>
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED
DATE 9:00 a.m.
APR 20 1995
DONALD W. KINNUNEN
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

**SURVEY &
REMONUMENTATION**
MAY 10 1995
COMMISSION

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Jamros, in a field survey on October 12, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K1: PLS-John Burt, DS, 1841, Set Post Corner of Sections 1 and 2 - N.Pine 4", N.57 W., 38 links, N.Pine 5", N.21 E., 22 links. PLS-Francis Coleman, DS, 1851, N.Pine 5", S.16 E., 24 links, N.Pine 8", S.77 W., 17 links. Subsequent resoration by author unknown. Robert L. Jamros, RLS, 1987, Found 6" x 6" Granite Marker Scribed "U.S.L.H.E." on the top of granite marker. References: W.Pine 12", S.23 E., 29.3 ft., W.Pine 10", N.67 W., 15.9 ft., R.Pine 12", S.71 W., 54.2 ft., W.Pine 12", N.64 E., 13.2 ft., Recorded in corner record No. 3-358 Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K1: Found in place a 6"x 6" granite marker scribed "U.S.L.H.E." on top. From existing monument found original GLO BT's in SW and NW positions, dead and down. Scribing and notch still visible. Found all Bearing Trees from 1987 report in excellent condition. Accepted existing monument and renewed existing reference trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K1: Set 5/8" x 5" Rebar w/ 3 1/4" Alum. Cap stamped to identify corner position, drilled and grouted into the top of existing granite monument. Renewed existing reference trees w/ BT signs and paint. Set PK nails for measure w/ brass I.D. washers in the following references trees. Ex. W.Pine 12", N.63 W., 16.03 feet, "S35 BT", Ex. R.pine 14", S.75 W., 54.13 feet, "S2 BT", Ex. W.pine 14", S.18 1/2 E., 29.25 feet, "S1 BT", Ex. W.Pine 16", N.68 E., 13.13 feet, "S36 BT", Steel witness post with Survey marker sign, NE, 2.0 feet, All bearings are magnetic.

Signed by Robert L. Jamros Date 12 April, 1995
Surveyor's Michigan License No. 25849