

SURVEY & REMONUMENTATION

FEB 19 1998

Approved by Alger County Land Survey Remonumentation Peer Group Under Act 245 of P.A. of 1990 On 12-10-1997

Donald W. Kinnunen Chairman

SECTION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

05-75

For corners in (County) Located In: Corner Code #
1. Public Land Survey T 49 R 13 K2
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R
4. Lot No. , Recorded Plat
5. Private Claims

FILED TIME 8:30 AM

DEC 17 1997

DONALD W. KINNUNEN REGISTER OF DEEDS ALGER COUNTY, MI

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 1-13. A dot is present in cell J2.

I, Robert L. Janros, in a field survey on November 18, 1997, 19 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K2: PLS - Francis Colman, DS, 1851 * Set quarter section post on left bank of stream, 25 links C NW * Tamarack 7, N.08 W., 29 links * White Pine 8, N.09 E., 21 links * Note on Random line of Francis Coleman states 'I apprehend that my men have made short measure on this line, but must establish it according to their measure' * From township line on corrected line, 5.0 07' West, 38.24 chains - enter wet marsh * 42.40 chains - set quarter section post * 82.40 chains - set post corner of Sections 1, 2, 11 and 12 (1997 - this is a partial description of calls along line) ***** No other subsequent restoration on record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K2: Located corner position by field survey * Position lies on the Northerly edge of a low, grassy clearing located in a replanted pine plantation * From corner position no evidence was found at original GLO BT locations * Evidence of local paint or blazing at or away from corner position, none was found * Corner position was established on true line at single proportionate measurement according to original GLO notes * Corner position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K2: Set Berntsen Alum. monument no. A1N230, stamped to identify corner position * Established reference trees w/BT signs, blazed and scribed * Set PK nails w/Alum. I.D. washers in the following - Jack Pine 8, S.47 W., 74.5 feet, '1/4S BT' * Red Pine 20, N.74 E., 51.7 feet, '1/4S BT' * Red Pine 16, S.63 E., 3.4 feet, '1/4S BT' * White Pine 13, N.59 W., 21.0 feet, '1/4S BT' * Survey marker sign on 6 foot steel post, N.39 W., 1.2 feet * All bearings are magnetic.

Signed by Robert L. Janros Surveyor's Michigan License No. 25849

Date 12/10/1997

