

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 4-8 1995

Donald W. Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-282

For corners in

Alger

(County)

Located In:

Corner Code #

1. Public Land Survey T 49N R 13W K3
T _____ R _____
T _____ R _____ SURVEY &
T _____ R _____ REMONUMENTATION
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____ MAY 10 1995
Property in Sec. S _____ T _____ R _____
- COMMISSION

FILED
...E 9:00 a.m.

APR 20 1995

DONALD W. KIRKUNEN
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Jamros, in a field survey on October 24, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K3: PLS-Francis Coleman, DS, 1851, Set post corner of sections 1,2,11 and 12, - Cedar 8", N.21 E., 26 links, Cedar 10", N.22 W., 34 links. A.C.R.C., H.H.Anderson,CE, 1935, Road alignment of Grand Marais East. Corner position noted by scale 959 ft. N. of centerline of road. No references given. Robert L. Jamros, RLS, 1987, Established corner by proportionate measurement. References: W.Birch 12", North, 69.75 ft., W.Birch Twin, 10'-12", N.08 W., 69.30 ft., W.Birch 16", N.20 E., 59.95 ft. Recorded in corner record No. 3-359, Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K3: Found corner position with 1" Iron Pipe and RLS cap in Tagalder marsh approx. 600 ft. N. of the Sucker River. Corner position as stated in corner record no. 3-359 was set by double proportionate measurement and Section corners one mile west, one mile north, one mile east, and 1/4 section corner one-half mile south. A search was made for original GLO evidence with no positive results. Bearing trees of the 1987 report found in excellent condition. No other bearing objects are available. Corner lies on the southern edge of a small knoll in the open Tagalder marsh. Existing corner position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K3: Set 2 1/4" x 30" Alum. Monument w/ 3 1/4" Alum. Cap over top of existing 1" Iron pipe. Stamped cap to identify corner position. Renewed existing reference trees w/ BT signs and paint. Set PK nails for measure w/ brass I.D. washers in the following reference trees. Ex. W.Birch 10", N.06 1/2 W., 69.21 feet, "S2 BT", Ex. W.Birch 12", N.02 E., 69.74 feet, "S2 BT", Ex. W.Birch 18", N.20 E., 59.96 feet, "S1 BT", Steel witness post with Survey marker sign, S.46 W., 1.0 feet, All bearings are magnetic.

Signed by

Robert L. Jamros

Date

12 April, 1995

Surveyor's Michigan License No.

25849