

SURVEY & REMONUMENTATION

FEB 19 1998

Approved by Alger County Land Survey Remonumentation Peer Group Under Act 843 of P.A. of 1990 On 12-10-1997

Donald W. Carlson
Chairman

SECTION

0574

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in _____

(County)

Located In:

Corner Code #

- | | | | | | |
|--------------------------------------|---|----|---|----|----|
| 1. Public Land Survey | T | 49 | R | 13 | K4 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Section | S | | T | R | |
| | S | | T | R | |

FILED
TIME 8:30 AM

DEC 17 1997

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jamros, in a field survey on August 04, 1997, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K4: PLS - Francis Colman, DS, 1851 * 40.00 chains, top of bank 150 feet C ENE and WSW and set quarter section post * Maple 12, N.33 E., 13 links * Fir 12, S.40 W., 26 links **** Robert L. Jamros, RLS, 1995 * Established corner position on true line at the mid point between section corners North and South * Found 4 inch squared post, author unknown * Set 1 inch iron pipe w/RLS cap and established witness trees * Unrecorded report **** No other subsequent restoration on record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K4: Found 1 inch iron pipe w/cap, 4 inch squared post and 4 existing BT's * Paint lines running in all cardinal directions from corner monument * Installed new monument and Renewed exist. BT's * Corner position as found is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K4: Replaced 1 inch iron pipe with a Berntsen Alum. monument no. A1NB30, stamped to identify corner position * Renewed exist. reference trees, scribing still visible, with BT signs and paint * Set PK nails w/Alun. I.D. washers for measure in the following - Maple 13, S.01 E., 5.82 feet, 'S 12 BT' * Maple 8, S.48 W., 20.07 feet, 'S 11 BT' * Beech 7, N.01 E., 4.02 feet, 'S 11 BT' * Maple 11, S.69 E., 12.63 feet, 'S 12 BT' * Survey marker sign on 6 foot steel post, N.63 E., 1.1 feet * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12/10/1997

