

**SURVEY &
REMONUMENTATION**

FEB 19 1998

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 845 of
P.A. of 1990 On 12-10-1997

**SECTION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

05-73

For corners in _____

(County)

Located In:

Corner Code #

- | | | | | | |
|---------------------------------------|---|-----------|---|-----------|-----------|
| 1. Public Land Survey | T | <u>49</u> | R | <u>13</u> | <u>K5</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | | | | |
| 5. Private Claims _____ | | | | | |

FILED
TIME 8:30 Am

DEC 17 1997

**DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI**

Register of Deeds Stamp & File Number

I, Robert L. James, in a field survey on October 21, 1997, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K5: PLS - Francis Colman, DS, 1851 * Set post corner of Sections 11, 12, 13 and 14 * Sugar 12, N.56 E., 15 links * White Birch 10, S.63 W., 24 links **** Billy D. Buckler, RLS, M.D. of C., Land Corner Record, 1960 * Set 1 inch iron pipe w/4 inch brass cap * This corner was replaced at wood post. Distances to streams and corners in vicinity check fairly well * Witnesses - Soft Maple 8, S.45 W., 137 links * Jack Pine 18, S.73 E., 49 links * Recorded in Liber 2, Page 98, Alger County Corner Records **** R.J. Radcliffe, RLS, C.C.I. Co., Land Corner Record * Recovered 1 inch iron pipe w/brass cap set by Billy D. Buckler, RLS, and witness trees * Red Maple 8, S.45 E., 137 links * Jack Pine 18, S.73 E., 49 links * Unrecorded report. **** No other subsequent restoration on record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K5: Found 1 inch iron pipe w/4 inch brass cap as set in 1960 * Recovered exist. reference trees and old wood post standing at monument * A search was made in both GLO original BT locations, evidence is lost * Measurements to adjacent corners check well and corner position was accepted locally and used. * Monument at corner position is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K5: Exist. 1 inch iron pipe w/brass cap, stamped to identify corner position * Renewed exist. BT's w/BT signs and paint and established additional reference trees * Set PK nails w/Alum. I.D. washers for measure in the following - Exist. BT, Jack Pine 32, S.66 E., 32.97 feet, scribing visible * Exist. BT, Maple 16, S.51 W., 90.04 feet, scribing not visible * Maple 6, N.83 E., 55.42 feet, *S 12 BT* * Red Pine 12, N.21 W., 5.84 feet, *S 11 BT* * Survey marker sign on 6 foot steel post, S.18 W., 1.0 feet * All bearings are magnetic.

Signed by Robert L. James
Surveyor's Michigan License No. 25849

Date 12/10/1997

