

**SURVEY &  
REMONUMENTATION**

FEB 23 1999

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

05-102

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 12/16 1998

Mc Davis RLS  
Chairman

For corners in

|                                       |                         |               |
|---------------------------------------|-------------------------|---------------|
| <u>Alger</u><br>(County)              | Located In:             | Corner Code # |
| 1. Public Land Survey                 | T49N R13W               | K6            |
|                                       | T _____ R _____         | _____         |
|                                       | T _____ R _____         | _____         |
|                                       | T _____ R _____         | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |

FIELD  
TIME 10:00 A.M.

JAN 8 1999

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

|    |    |   |    |   |    |   |    |   |    |   |    |   |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

I, Robert L. Jamros, in a field survey on August 13, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

**K6:** P.L.S. - Francis Colman, DS, 1851. Set quarter section post. Fir 6, N.61°W., 50 links. Maple 5, S.9°E., 33 links. \*\*\*\*\* Billy D. Buckler, RLS, 1960. Set corner monument, 1" G.I.P. with 4" brass cap, midway and on line between section corners. Witnesses, 8" Soft Maple (1/4S NBT), S.80°W., 32 links, 6" Soft Maple (1/4S NBT), S.19°E., 24 links. \* Liber 2, Page 97, Alger County Corner Records. \*\*\*\*\* C.C.I. Co. Land Corner Records, J.R. Radcliffe, RLS, 1966. Found monument and all BT's of the 1960 report in good condition. No new witnesses were made. \*\*\*\*\* No other record of restoration.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

**K6:** Located corner position by standard field survey and single proportionate measurement. Found monument and accessories of the 1960 report in good condition and in acceptable position. Established additional references. Monument as found is accepted as a careful and faithful reestablishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**K6:** Existing 1" G.I.P. with 4" brass cap. Established 3 new reference trees with BT signs, blazed, scribed and painted. Renewed 1 existing reference tree with BT signs and paint. Set PK nails for measure with aluminum I.D. washers in the following reference trees. \* Existing - Maple 8", S.19°E., 16.48 feet; \* Maple 10", S.75°W., 26.45 feet, \*1/4S BT"; \* Maple 6", N.49°W., 32.79 feet, \*1/4S BT"; \* Jack Pine 4", N. 72°E., 10.48 feet, \*1/4S BT"; \* Survey marker sign on 6 foot steel post, S.45° W., 1.0 feet. All bearings of new references are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date December 16, 1998

