

**SURVEY &
REMONUMENTATION**

FEB 23 1999

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12/16/1998

McL. Jamros RLS
Chairman

**SECTION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

05-103

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T49N R13W	K7
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED
TIME 10:00 AM

JAN 8 1999
DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on August 13, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

K7: P.L.S. - Francis Colman, DS, 1851. Set post corner of Sections 13, 14, 23 and 24. Sugar 13, N.35°E., 22 links. Sugar 12, S.33°W., 43 links. ***** Billy D. Buckler, RLS, 1960. This corner was reestablished on line with single proportionate measurements between section corners. Original survey ran 6 miles E and W random dividing township. Set 1" G.I.P. with 4" brass cap. Witnesses, 8" Soft Maple (S23 NBT), S.54°W., 43 links * 6" Soft Maple (S13 NBT), N.22°E., 41 links. Liber 2, Page 103 Alger County Corner Records. ***** C.C.I. Co. Land Corner Records, J.R. Radcliffe RLS, 1966. Found monument and all BT's of the 1960 report in good condition. No new witnesses were made. ***** No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K7: Located corner position by standard field survey and proportioned distances from corners North and East-West from corner position. Found monument and accessories of the 1960 report in good condition and in acceptable position. Established additional references. Monument as found is acceptable as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K7: Existing 1" G.I.P. with 4" brass cap. Established 2 new reference trees with BT signs, blazed, scribed and painted. Renewed 2 existing reference trees with BT signs and paint. Set PK nails for measure with aluminum I.D. washers in the following reference trees. * Existing - Maple 14", N.22°E., 27.35 feet; * Existing - Maple 12", S.54°W., 28.64 feet, * Maple 8", N.32°W., 5.68 feet, *S14 BT", * Maple 10", S.40°E., 8.53 feet, *S24 BT". * Survey marker sign on 6 foot steel post, N.45°E., 0.90 feet. All bearings of new references are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date December 16, 1998

