

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 4-8 1995

Marcus W. Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-278

For corners in

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>13W</u>	<u>L1</u>
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

FILED
TIME 9:00 a.m.

APR 20 1995

DONALD W. KINNUNEN
REGISTERED PROFESSIONAL
Register of Deeds Stamp & File Number

**SURVEY &
REMONUMENTATION**
MAY 10 1995
COMMISSION

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Jamros, in a field survey on October 21, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L1: PLS-John Burt, D5, 1841, Set Qr. Section Post- N.Pine 6', N.28 E., 13 links, N.Pine 6", N.43 W., 45 links. No other Subsequent Restoration found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L1: Began at BT corner of Sections 1 and 2, T.49N., R.13W. Ran corrected compass line on a GLO bearing East for a distance of 40.0 chains. Found 10" Pine stub in N.43 W., position at 45 links with blaze scar, axe marks and measuring notch still visible. Found dead and down 12" Pine in N.28 E., position at 8.58 ft. Area of blaze, notch and scribing rotted away. Established corner position from remains of GLO BT's and set monument and references. Area around corner position is a open Red Pine and Jack Pine plantation and there is evidence of the area being badly burnt over in the past.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L1: Set 2 1/4" Alum. Monument w/ 3 1/4" Alum. Cap stamped to identify corner position. Established reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ brass I.D. washers in the following reference trees. J.Pine 6", N.29 W., 23.15 feet, "1/4s BT", J.Pine 6", N.73 E., 13.75 feet, "1/4s BT", J.Pine 6", S.58 W., 18.56 feet, "1/4s BT", J.Pine 6", S.16 E., 28.42 feet, "1/4s BT", Steel witness post with Survey marker sign, S.38 E., 1.5 feet, All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12 April, 1995