

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 4-8 1995

Gerald Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-283

For corners in

Alger

(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|-----------|
| 1. Public Land Survey | T <u>49W</u> R <u>13W</u> | <u>L3</u> |
| | T _____ R _____ | |
| | T _____ R _____ | |
| | T _____ R _____ | |
| | T _____ R _____ | |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

**SURVEY &
REMONUMENTATION**

MAY 10 1995

COMMISSION

FILED

9:00 a.m.

APR 20 1995

DONALD W. WINNUP
REG. SURV. GEN. STATE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, Robert L. Janros, in a field survey on October 24, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L3: PLS-Francis Coleman, DS, 1851, Set Qr. Section Post- Fir 12", N.44 E., 18 links, Maple 8", S.69 W., 36 links. No Subsequent Restoration. Robert L. Janros, RLS, 1987, Established corner on line at proportionate distance between Section corners east and west., References: Maple 14", S.10 W., 6.9 ft., Maple 8", N.57W., 12.0 ft., Maple 14", N.16 E., 23.0 ft., Maple 5", N.86 E., 6.2 ft., Recorded in record No. 3-359, Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L3: Found corner position with 1" Iron Pipe and R.L.S. cap in level open hardwoods. Corner record no. 3-359 states that corner was set by single proportionate measurement between section corners. Bearing trees of the 1987 report found in excellent condition. From monument established GLO BT locations and made search, results inconclusive. Found evidence of old paint and blaze lines to the East, West and North of corner position. Existing corner position accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L3: Set 2 1/4" x 30" Alum. Monument w/ 3 1/4" Alum. Cap over top of existing 1" iron pipe. Stamped cap to identify corner position. Renewed existing reference trees w/ BT signs and paint. Set PK nails for measure w/ brass I.D. washers in the following reference trees. Ex. Maple 15", S.05 W., 5.88 feet, "1/4 12 BT", Ex. Maple 8", N.57 W., 11.98 feet, "1/4 1 BT", Ex. Maple 14", N.16 E., 23.06 feet, "1/4 1 BT", Twin Maple 10" & 13", N.61 E., 36.90 feet, "1/4s BT", Steel witness post with Survey marker sign, S.39 W., 1.5 feet. All bearings are magnetic.

Signed by

Robert L. Janros
25849

Date

12 April, 1995

Surveyor's Michigan License No.