

DEC 27 1999

For corners in

SECTION

ALGER

(County)

Located In:

Corner Code #

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Alger County Land Survey Board... Peer Group Under Act 74 of P.A. of 1990 On 12-2-1999

Gerald W. Carlson Chairman

05-150

- 1. Public Land Survey T 49N R 13W L9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R
4. Lot No. , Recorded Plat
5. Private Claims

FILED TIME 1:30 p.m.

DEC 15 1999

DONALD W. KINNUNEN REGISTER OF DEEDS ALGER COUNTY, MI

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on July 22, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L9: PLS \* Francis Colman, DS, 1851. \* Set quarter section post. \* Fir 6', N.27 E., 31 links. \* Maple 6", S.30 W., 4 links. \*\*\*\* Michigan Department of Conservation, Forestry Division. \* Billy D. Buckler, RLS, 1960. \* Set 1" iron pipe with 4" brass cap midway and on line between section corners. \* 6" Aspen (1/4s NBT), N.30 W., 37 1/2 links. \* 18" W.Pine stub (1/4s NBT), S.79 E., 20 links. \* Liber 2, Page 99, Alger County Corner Records. \*\*\*\* No other subsequent restoration of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L9: Located corner location by calculated position and standard field survey methods and found location to be in the center of a North-South track road. Monument and references of the 1960 report have been destroyed and lost. Established corner position at mid point and on line between section corners. Set monument at established corner position and is accepted as a careful and faithful reestablishment of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L9: Set 2 1/2"x30" Berntsen aluminum monument N. A1NB30 with 3 1/4" aluminum cap stamped to identify corner position. \* Established the following reference trees with BT signs, blazed, scribed and painted. \* Set PK nails for measure with aluminum I.D. washers in the following: J.Pine 8", N.80 E., 62.78 feet, '1/4s BT'. \* J.Pine 8", S.32 E., 62.80 feet, '1/4s BT'. \* W.Cherry 5", S.54 W., 44.09 feet, 'BT'. \* Balsam 5", N.44 W., 43.50 feet, 'BT'. \* Survey marker sign on 6 foot steel post, S.84 E., 8.0 feet. \* All bearings are magnetic.

Grid table with columns A-M and rows 1-13. Cell (9, L) contains a black dot.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date Dec 13, 1999

