

SURVEY & REMONUMENTATION

JUL 30 1996

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 5/8 1996

Donald W. Kinnunen
Chairman

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

4-368

For corners in _____ Located In: _____ Corner Code # _____
Alger (County)

- | | | | | | | | |
|--------------------------------------|---|-----|---|-----|----|--|--|
| 1. Public Land Survey | T | 49N | R | 13W | M2 | | |
| | T | | | R | | | |
| | T | | | R | | | |
| | T | | | R | | | |
| 2. Property Controlling in Section | S | | T | | R | | |
| | S | | T | | R | | |
| 3. Miscellaneous Property in Section | S | | T | | R | | |
| | S | | T | | R | | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

FILED
TIME 3:00 p.m.

JUN 27 1996

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jamros, in a field survey on March 06, 1996, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M2: PLS-John Burt, DS, 1841, Set qr. section post - Cottonwood 2", S.84 E., 29 links, Aspen 10", N.14 W., 35 links.***** Michigan Department of Natural Resources, Billy D. Buckler, RLS, 1975, Corner re-established on line and by single proportion measure. Found squared post 7.35 feet north and 3.95 feet west of corner position. Set 1" iron pipe with 4" Aluminum cap, Established the following references - W.Pine 10", S.25 W., 22.4 feet, R.Pine 14", N.27 W., 42.7 feet. Recorded in Liber one on page 215, Luce County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M2: Found 1" G.I.P. with 4" Aluminum cap and a 4" flat faced wood post, scribed. Also found two existing bearing trees as described in the report of 1975. Existing W.Pine BT in the southwest position is now a dead stub. Information acquired from the Michigan DNR documenting the method at which corner position was reestablished follow accepted methods. Renewed existing bearing tree to current Alger County standards and established additional reference trees. Monument is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M2: Stamped P.A. 345 in existing four inch Aluminum capped Department of Conservation Monument. Renewed existing reference tree w/ BT signs and paint. Established additional reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ Alum. I.D. washers in the following reference trees. Ex. Red Pine 20", N.21 W., 42.85 feet, " 1/4s NBT ", Red Pine 8", N.43 E., 50.54 feet, " 1/4s BT ", Red Pine 15", S.51 E., 54.92 feet, " 1/4s BT ", Red Pine 7", S.24 W., 25.92 feet, " 1/4s BT ", Survey marker sign on six foot steel post, S.68 W., 1.0 feet. All bearings are magnetic.

Signed by Robert L. Jamros

Date 12 June 27 1996

Surveyor's Michigan License No. 25849

