

SURVEY & REMONUMENTATION

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 5/18 1996

JUL 30 1996

Gerald W. Carlson
Chairman

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

4-369

For corners in Alger (County) Located In: Corner Code #

- | | | | | | |
|---|---|-----|------|----|--|
| 1. Public Land Survey | T | 49N | R13W | M3 | |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling
in Section | S | T | R | | |
| | S | T | R | | |
| 3. Miscellaneous
Property in Section | S | T | R | | |
| | S | T | R | | |

FILED
TIME 3:00 p.m.

JUN 27 1996

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Robert L. Jamros, in a field survey on March 05, 1996, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M3: PLS-John Burt, DS, 1841, Set post corner of sections 1 & 12 - 8.Ash (no size given), S.65 E., 32 links, 8.Ash 12", N.57 W., 18 links, B.Ash 12, N.54 E., 45 links, B.Ash 12, S.57 W., 9 links.**** CCI Forestry Division, Land and Timber Examination Report, T.J.McLaren, 1950, Indicates a two inch iron pipe at corner position. No references were given.**** Michigan Department of Conservation, Forestry Division, Billy D. Buckler, RLS, 1953, Corner pointed out to me by B. McTiver, district forester in Newberry. Three original BT's still in place, poor condition. Set 1" pipe w/ 4" brass cap and established the following references, Balsam 10", S.32 W., 22 links, Balsam 8", N.68 E., 22 links. Recorded in Liber one on page 109A, Luce County Records. No other subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M3: Found 1" G.I.P. with 4" Brass cap driven in center hole of a 2" iron pipe high above the ground and unstable. Drove monument and pipe down to stable condition. Found BT's of the report of 1953 dead and down. Also found three other unrecorded BT's from a more recent survey in good condition, blazed and scribed. Established an additional BT and upgraded existing BT's to current Alger County standards. Monument position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M3: Stamped P.A. 345 in existing four inch brass capped Department of Conservation Monument. Renewed existing reference trees w/ BT signs and paint. Established additional reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ Alum. I.D. washers in the following reference trees. Ex. Balsam 16", S.82 W., 14.67 feet, " 12 BT ", Ex. Maple 10", N.42 W., 17.43 feet, " 1 BT ", Ex. Balsam 14", N.50 E., 21.46 feet, " 6 BT ", Maple 14", S.45 E., 45.58 feet, " 57 BT ". Survey marker sign on six foot steel post, S.23 W., 0.80 feet. All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12 June 1996
FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

