

SURVEY & REMONUMENTATION

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1960 On 5/8 1996

JUL 30 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

4-370

For corners in Alger Located In: _____ Corner Code # _____
(County)

- | | | | | | | |
|---|---|-----|---|------|----|--|
| 1. Public Land Survey | T | 49N | R | R13W | M4 | |
| | T | | | R | | |
| | T | | | R | | |
| | T | | | R | | |
| | T | | | R | | |
| 2. Property Controlling
in Section | S | | T | R | | |
| | S | | T | R | | |
| 3. Miscellaneous
Property in Section | S | | T | R | | |
| | S | | T | R | | |

FILED

TIME 3:00 p.m.

JUN 27 1996

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Robert L. Jamros, in a field survey on March 07, 1996, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M4: PLS-John Burt, DS, 1841, Set qr. section post - Sugar 6", S.08 E., 24 links, Sugar 6", N.58 W., 10 links.**** CCI Forestry Division, Land and Timber Examination Report, T.J. McLaren, 1950, Documented six inch post at corner position. No references were given.**** Michigan Department of Natural Resources, Billy D. Buckler, RLS, 1977, Corner re-established midway and on line between two section corners. No evidence of original corner. Set 1" pipe w/ 4" Aluminum cap and established the following references, Maple 20", N.62 W., 17.6 feet, Beech 12", S.47 E., 29.1 feet. Recorded in Liber one on page 238, Luce County Records. No other subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M4: Found 1' G.I.P. with 4" Aluminum cap and a 6" flat faced wood post three feet high. Also found two BT's from the report of 1977 in good condition. Corner position checks well with other corners of section 12 documented by a section subdivision survey performed in 1985 by Robert L. Jamros, PS, Established additional BT's and upgraded existing BT's to current Alger County standards. Monument position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M4: Stamped P.A. 345 in existing four inch aluminum capped monument. Renewed existing reference trees w/ BT signs and paint. Established additional reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ Alum. I.D. washers in the following reference trees. Ex. Maple 24", N.61 W., 18.33 feet, " Blzd ", Ex. Beech 16", S.44 E., 29.46 feet " BH Blz. NBT ", Maple 8", N.14 E., 59.52 feet " 1/4s BT ", Beech 12", S.37 W., 49.29 feet, " 1/4s BT ". Survey marker sign on six foot steel post, S.63 W., 1.0 feet. All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12/27/96

