

SURVEY & REMONUMENTATION

FEB 23 1999

Approved by Alger County Land Survey Re-monumentation Peer Group Under Act 345 of P.A. of 1990 On 12/16 19 98

Metz David RLS Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

05-106

For corners in

Form with fields for Alger (County), Located In: T49N R13W, Corner Code # M5, and numbered sections 1-5 for Public Land Survey, Property Controlling, etc.

Register of Deeds Stamp & File Number section containing TIME 10:00 A.M., JAN 8 1999, DONALD W. KINNUNEN REGISTER OF DEEDS ALGER COUNTY, MI

I, Robert L. Jamros, in a field survey on June 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13, containing numbers 1-36.

A. Description of original monument and accessories and/or subsequent restoration:

M5: P.L.S. - John Burt, DS, for William A. Burt, DS, 1841. Set post corner of Secs. 12 & 13. Birch 20, S.77°W., 4 links. Birch 12, N.77°E., 11 links. \*\*\*\* Billy D. Buckler, RLS, 1956. Replaced section corner as perpetuated by Marcus Schaaf, RLS No. 3104. Set 1" G.I.P. with 4" brass cap. Witnesses, 4" W. Pine, N.80°E., 23 links, 6" Soft Maple, N.01°E., 74 links. \* Liber 2, Page 141, Alger County Corner Records. \*\*\*\* C.C.I. Co. Land Corner Records. J.R. Radcliffe, RLS, 1966. Found monument and all BT's of the 1956 report in good condition. No new witnesses were made. \*\*\*\* No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M5: Located corner position by standard field survey and single proportionate measurements to adjacent corners. Found monument and accessories of the 1956 report in good condition and in acceptable position. Established additional references. Monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M5: Existing 1" G.I.P. with brass cap. Established 2 new reference trees with BT signs, blazed, scribed and painted. Renewed 2 existing reference trees with BT signs and paint. Set PK nails for measure with aluminum I.D. washers in the following reference trees. \* Existing - White Pine 24", N.80°E., 14.87 feet; \* Existing - Maple 9", S.01°E., 26.14 feet; \* Maple 5", S.48° W., 59.44 feet, "BT"; \* Maple 4", N.53°W., 40.68 feet, "BT". \* Survey marker sign on 6 foot steel post, S.85°E., 1.0 feet. All bearings of new references are magnetic.

Signed by Robert L. Jamros Surveyor's Michigan License No. 25849

Date December 16, 1998

