

SURVEY & REMONUMENTATION

JUL 30 1996

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 5/8 1996

Donald W. Kinnunen
Chairman

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

4-371

For corners in _____ Located In: _____ Corner Code # _____
Alger (County)

- | | | | |
|---|--------------|---------------|----------|
| 1. Public Land Survey | T <u>49N</u> | R <u>R13W</u> | M6 _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling
in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous
Property in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

FILED
TIME 3:00 p.m.

JUN 27 1996

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on March 07, 1996, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M6: PLS-John Burt, DS, 1841, Set qr. section post - Birch 14", S.50 E., 33 links, Hemlock 7", N.47 W., 29 links.***** CCI Forestry Division, Land and Timber Examination Report, David C. West, 1968, Documented a four inch LES post at corner position. No references given.***** Michigan Department of Conservation, Forestry Division, Billy D. Buckler, RLS, 1972, Found a Painted Cedar post set by the Land Economic Survey (LES) during the 1930's. Found blazes on live timber to North, South and East. Corner lies 20 feet East of a woods road. Placed 1" pipe with 4" Aluminum cap at corner and established the following reference trees. 8' Hard Maple, S.17 W., 9.3 ft., 24" W.Pine, N.71 E., 58.0 ft., Recorded in Liber one on page 112, Luce County Records. No other subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M6: Corner location found by measuring from corner to North one half mile South along existing woods road which parallels section line. At corner position found 1" G.I.P. with 4" Aluminum cap in good condition. Also found BT in Northeast location in good condition, BT in Southwest location has been destroyed. Logging operations of the past years destroyed original BT locations. Established additional reference trees and upgraded existing BT to current Alger County standards. Monument position is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M6: Stamped P.A. 345 in existing four inch brass capped Department of Conservation Monument. Renewed existing reference tree w/ BT signs and paint. Established additional reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ Alum. I.D. washers in the following reference trees. Ex. W.Pine 40", N.75 E., 58.96 feet, "Large Blaze", Beech 16", S.68 E., 61.83 feet, " 1/4s BT ", Maple 6", S.05 W., 18.11 feet, " 1/4s BT ", Maple 7", N.24 W., 50.45 feet, " 1/4s BT ". Survey marker sign on six foot steel post, S.46 E., 1.0 feet. All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12 1996

