

SURVEY & REMONUMENTATION

FEB 23 1999

Approved by Alger County Land Surveyor... Peer Group Under Act 845 of P.A. of 1990 On 2/16/99

SECTION

05-108

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for County (Alger), Located In (T49N R13W, T49N R12W), Corner Code # (M8, A8), and numbered items 1-5.

FILED TIME 10:00 AM JAN 8 1999 DONALD W. KINNUNEN REGISTER OF DEEDS ALGER COUNTY, MI Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13, containing numbers 1-36.

I, Robert L. Jamros, in a field survey on July 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules...

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M8: P.L.S. - John Burt, DS, for William A. Burt, DS, 1841. Set quarter section corner. Fir 8, S.41°E., 28 links. Mountain Ash 4, N.51°W., 21 links. \*\*\*\*\* No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M8: Located and established corner position by standard field survey and single proportionate measurement between BT section corners 1/2 mile North and South. Search was made for GLO evidence, inconclusive. Evidence of blaze lines to the North, South and West. Monumented corner position and established new reference trees. Position as monumented is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M8: Set Berntsen aluminum monument with 3 1/4" aluminum cap no. AINB30, stamped to identify corner position. Established the following reference trees with BT signs, blazed, scribed and painted. Set PK nails for measure with aluminum I.D. washers in the following reference trees. \* Maple 16", N.65°E., 25.37 feet, "1/4S BT"; \* Maple 6", S.20°E., 11.96 feet, "1/4S BT"; \* Maple 10", S.29°W., 15.10 feet, "1/4S BT"; \* Maple 12", N.37°W., 21.05 feet, "1/4S BT". \* Survey marker sign on 6 foot steel post, N.60°W., 1.0 feet. All bearings are magnetic.

Signed by Robert L. Jamros Surveyor's Michigan License No. 25849

Date December 16, 1998

