

**SURVEY &
REMONUMENTATION**

FEB 23 1999

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12/16 1998

Me. Davis RLS
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

05-109

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T49N R13W	<u>M9</u>
	T49N R12W	<u>A9</u>
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED
TIME 10:00 A.M.

JAN 8 1999
DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Jamros, in a field survey on July 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M9: P.L.S. - John Burt, DS, for William A. Burt, DS, 1841. Hemlock 22, corner of Sections 24 and 25, Spruce 13, N.52°W., 28 links. ***** Billy D. Buckler, RLS, 1960. This corner was replaced from evidence of blazes on old down Hemlock which may have been the corner tree in the original notes. Measurements to corners in vicinity check well. Set 1" G.I.P. with brass cap. Witnesses, 7" Soft Maple (S30 NBT), S.02°E., 51 links, 5" Soft Maple (S24 NBT), N.74°W., 16 links. * Liber 2, Page 107, Alger County Corner Records ***** C.C.I. Co., Land Corner Reports. J.R. Radcliffe, RLS, 1966. Found monument and all BT's of the 1960 report in good condition. No new witnesses were made. ***** No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M9: Located corner position by standard field survey and single proportionate measurements. Found monument of the 1960 land corner report in good condition and in the center of the remains of a Hemlock stump. Evidence of GLO Spruce BT in the Northwest position no longer remains. Established additional reference trees in addition to the 2 existing BT's of the 1960 report. Monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M9: Existing 1" G.I.P. with brass cap. Established 2 new reference trees with BT signs, blazed, scribed and painted. Renewed 2 existing reference trees with BT signs and paint. Set PK nails for measure with aluminum I.D. washers in the following reference trees. * Balsam 5", S.48°E., 26.51 feet, "S30 BT"; * Maple 8", N.34°E., 10.38 feet, "S19 BT"; * Existing - triple Maple 2", S.02°W., 34.35 feet; * Existing - Maple 8", N.74°W., 10.59 feet. * Survey marker sign on 6 foot steel post, N.70° W., 1.0 feet. All bearings of new references are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date December 16, 1998

