

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T 49 NR 137

Alger COUNTY

DESCRIPTION OF CORNER 1/4 cor. between secs: 23-26

DESCRIPTION OF CORNER MONUMENT 1" Pine with 4" Brass Cap

WITNESSES TO CORNER 20" W. line stub (1/4s NBT) N58°E 90 lks.

Re-marked original B.T.

36" W. Pine stp. (1/4s NBT) S55°W 42 lks.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced cor. from one W. Pine stump [probable B.T.]. Found old face, notch and overgrowth. Stump has burned. Found several other faces on stump. Position fits stream to east and west. Cor. lies on top of bank and 1 ch. west of Sucker River. Found by Forestry Division Survey Crew. Cor. placed and wit. 6/26/58 with Frank Bray.

SURVEYORS SEAL

SIGNED *Billy D. Buckler*  
Billy D. Buckler  
REGISTERED LAND SURVEYOR

DATE 7/30/59