

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 49. NR. 13. W.

ALGER COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sections 25 and 36

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 28" W. Pine Stp. (1/4s NBT) N 70° E 29 Links

34" W. Pine Stp. (1/4s NBT) N 5° E 99 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by single proportionate measure between section corner 39.54 chains west and W. Pine Line tree 27.47 chains east.

Corner was placed and witnessed May 18, 1960 with Frank J. Bray.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 5/23/60  
REGISTERED LAND SURVEYOR  
Billy D. Buckler