

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T ~~4849~~ NR 13 W

Alger COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 2, 3, 34, 35

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 13" Hard Maple (S 3 NBT) S 17° W 53 Links

13" Soft Maple (S 35 NBT) N 75° E 16 1/2 Links

9" Hard Maple (S 34 NBT) N 58° W 38 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one Sugar B. T. bearing N 14° E 45 Links. Tree is green and standing, has been chopped out around both faces. Found post set by C.C.I. men. Corner found by Frank J. Bray.

Corner was placed and witnessed May 19, 1960 with Frank, J. Bray.

SURVEYORS SEAL

SIGNED

*Billy D. Buckler*  
REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 5/23/60