

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T..49. NR..13..W

Alger COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 23,24,25,26

DESCRIPTION OF CORNER MONUMENT 1" Iron Pipe with 4" Brass Cap

WITNESSES TO CORNER 8" Black Cherry (S 24 NBT) N 26° E 11 Links

18" W. Pine Stub (S 23 NBT) N 45° W 59 Links

28" W. Pine Stump (S 25 NBT) S 87° E 148 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by setting it on line and proportionate measurement between corners set on 3 mile random as per original survey notes.

Corner was placed and witnessed June 29, 1960.

SURVEYORS SEAL

SIGNED

REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 7/21/60