

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 49. NR. 13. W

A l g e r COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 14, 15, 22, 23.

DESCRIPTION OF CORNER MONUMENT 1" Iron Pipe with 4" Brass Cap

WITNESSES TO CORNER 7" Aspen (S 22 NBT) S 08° W 68 Links

8" Aspen (S 15 NBT) N 78° W 84 1/2 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by placing it on line and single proportionate measurement between corners set on East, west line dividing township as per original notes.

Corner was placed and witnessed June 27, 1960.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 2/21/60  
REGISTERED LAND SURVEYOR  
Billy D. Buckler