

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49. NR. 13. W

Alger COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 26, 27, 34, 35

DESCRIPTION OF CORNER MONUMENT 1" Iron Pipe with 4" Brass Cap

WITNESSES TO CORNER 30" W. Pine Stump (S 35 NBT) S 36° E 173 1/2 Links

40" W. Pine Stump (N B T) N 84° W 103 Links

26" W. Pine Stump (S 34 NBT) S 25° W 150 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by placing it on line and single proportionate measurements between corners set on each end of 3 mile randoms as run in original survey.

Corner was placed and witnessed June 28, 1960.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 7/21/60
REGISTERED LAND SURVEYOR
Billy D. Buckler