

JAN 18 2001

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alger
(County)

Located In:

Corner Code #

- | | | | | | |
|---------------------------------------|---|-----|---|-----|-----|
| 1. Public Land Survey | T | 49N | R | 13W | I12 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | |
| | S | | T | | |
| 3. Miscellaneous Property in Section | S | | T | | |
| | S | | T | | |
| 4. Lot No. _____, Recorded Plat _____ | | | | | |
| 5. Private Claims _____ | | | | | |

Approved by Alger County
Land Survey Re-monumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12-13-2000

Heard Colman
Chairman

05-198

FILED
TIME 8:50 Am

DEC 20 2000

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on August 24, 2000

do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I12: PLS Francis Colman, DS, 1851. Set quarter section post. Fir 10", N.77°E., 7 links. W. Birch 5", S.39°W., 32 links. ***** Michigan Department of Conservation, Forestry Division. Billy D. Buckler, RLS, 1960. Set 1" iron pipe with 4" brass cap midway and on line between section corners. W. Pine stump, 14" (1/4S BT) N.36°E., 63 links. W. Pine stump 36" (1/4S NBT) N.66°W., 70 links. Liber 2, Page 105, Alger County corner records. No other subsequent restoration of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I12: Found 1" iron pipe with 4" brass cap and 2 NBT's of the 1960 report in good condition. Corner monument as found lies 0.3 feet West and 6.7 feet North of midpoint position between section corners. No original corner evidence found. Existing corner monument as found is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I12: Existing 1" iron pipe with 4" brass cap as found. Renewed existing NBT's with BT signs and paint. Established additional reference trees with BT signs, blazed, scribed and painted. Set PK nails for measure with aluminum I.D. washers in the following: Ex. NBT, W. Pine stump 14", N.41°E., 41.26 feet; Ex. NBT, W. Pine stump 36", N.58°W., 46.75 feet; W. Cherry 11", S.81°E., 53.39 feet (1/4S BT); W. Cherry 20", S.32°W., 38.97 feet (1/4S BT). Survey marker sign on 6 foot steel post, South 1.5 feet. All bearings are magnetic.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Signed by Robert L. Jamros

Date Dec. 17, 2000

Surveyor's Michigan License No. 25849

