SURVEY & REMONUMENTATION

Approved the Land Survey Structure Interior Peer Group Lines/Act 843 of P.A. of 1930 Ca. 12-101997

FEB 1 9 1998

05-54

Heald W. alson

LAND CORNER RECORDATION CERTIFICATION

Chaman		ent of Act 74, Mich. P.A	•
For corners in	-	•	
Sountyi	Located In:	Comer Code #	FILED
Public Land Survey	40 15 T <u>131</u> R 1510	Ģ I	TIME 8:30 A.M.
T. Table Land Garrey	T R	<u> </u>	DEC 17 1997
	T R S T R S T R		DONALD W. KINNUNEN REGISTER OF DEEDS GER COUNTY, MI
3. Miscellaneous S Property in Section S	S T R S T R		Register of Deeds Stamp & File Number
4. Lot No, Recol			A B C D E F G H J K L 2 6 5 4 3 - 2 1 1 - 3 4 7 - 3 8 9 10 11 12 12
do hereby certify that under requirer in lines 1 and 2 above were in conformanual of survey instructions of Management or by a decree of a Co 5 above were in conformance with Decree of a Court of Law; establishes expressed below:	ments of P.A. 74, Michigan P.A. of mance with regulations and rule the United States Department out of Law and/or that the come the rules of the Michigan Board	of 1970, the corner points menti- is therefore as required in the cu- t of the Interior, Bureau of er points mentioned in lines 3, 4 d of Professional Surveyors or	oned 6 18 17 16 15 14 13- Irrent 7
NOTE: Not more than 4 corners on this certificate.	s, all in the same town and ra	nge, may be recorded	12 31 32 33 34 35 36
A. Description of original mon	ument and accessories and	or subsequent restoration:	•
51: PLS - Jiht Burt, DS, 1841	Est post corner of Section	s f and 6 k White Pine 16,	N.40 E., 7 links = white Pine 16, N.25 W., 26
-links **** George E. Adair. Di	5. 1851 * White Pine 28 🗦 4	F F F9 links ± White Dine	24. S.18 L. 39 Hoxe xxxxx Dean C. DelaMater

RLS, Michigan Department of Conservation, 1953 * Established corner position from 4 original BY's still in place, 1 in fair condition, 3 in poor conditions # Set 1 inch pipe w/ 4 inch brass can # Made the following witness's - White Fine accump 28, N.23 W., 55 links # White Pine stump 35, S.10 E., 73 links * Recorded in Liber 1. Page 39, Aiger County records. **** Ac other subsequent restoration on record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

61: Found . iron gary, iron pipe w/brass cap * Located original BT positions and found 3 stumps of the 4 originals * Recovered both BT's from the 1953 report - White Pine stump in the Southeast position in poor condition and White Pine stump in the Northwest position badly decayed a Satablished 4 reference trees a Monumented position as found is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C1: Exist.1 incm galv. iron pipe w/brass cap as stamped to identify corner position. Corner lies approx. 100 feet South of a East-West track road = Established the following reference trees w/ET signs, blazed, scribed and painted. Set PX halls for measure w/Alum. I.D. washerd in the following - Red Pine 8, S.75 M., 26.67 feet, "86 BT" * Maple 5, M.56 M., 13.43 feet, "831 ET" * Red Pine 8, M.13 E., 13.85 feet. '322 BT' * Red Pine 7, 8.07 E., 6.93 feet, '35 BT' * Survey marker sign on 6 foot steel post, 8.35 W., 1.0 feet * All bearings are tagnetic.

Signed by

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESS

REVISED MAY 14, 1975 REVISED JAN., 1963