

DEC 27 1999

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12-2-1999

Gerall Wilson
Chairman

05-164

For corners in **SECTION** **LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>15W</u>	D1
	T <u>49N</u> R <u>15W</u>	D13 ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED
TIME 1:30 AM.
DEC 15 1999
DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jamros, in a field survey on July 01, 1999, 19_____, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, _____ recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D1: PLS * John Burt, OS, 1841. * Set quarter section post. * W.Pine 28', N.19 E., 26 links. * W.Pine 16', N.11' W., 44 links. **** C.C.I. Co., Land Corner Record. * Ray J. Brotherton, RLS, 1952. * Found stumps of both original pine BT's. * No corner material given. * Witnesses: W.Pine 12', N.85.5 W., 81.5 links. * W.Pine 12', S.53E., 92 links. * Unrecorded. **** Michigan Department of Conservation, Forestry Division. * Dean C. DeLaMater, RLS, 1954. * Corner had been previously located and perpetuated by Ray J. Brotherton, RLS. * 2 original BT's still in place, in good condition. * Set 1' iron pipe with 4" brass cap. * 12' W.Pine, S.50 E., 92 links. * 12' W.Pine, N.85 W., 82 links. * Liber 2, Page 71, Alger County Corner Records. **** No other subsequent restoration of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D1: Located corner search area by calculated position and standard field survey methods. Found 1' iron pipe with 4" brass cap and only 1 BT of the 1954 report. Stumps of the original BT's are still evident, in poor condition. Established additional reference trees. Corner monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D1: Existing 1' iron pipe with 4" brass cap. * Renewed existing and established additional reference trees with BT signs, blazed, scribed and painted. * Set PK nails with aluminum I.D. washers for measure in the following: R.Pine 7", S.31 E., 47.98 feet, '1/4s BT". * W.Pine 6", N.40 E., 19.64 feet, '1/4s BT". * R.Pine 5", S.58 W., 16.55 feet, '1/4s BT". * Existing - W.Pine 36", N.80 W., 54.00 feet, '1/4s BT". * Survey marker sign on 6 foot steel post, S.11 W., 1.6 feet. * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date Dec 13, 1999

