

**SURVEY &
REMONUMENTATION**

FEB 23 1999

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12/16 1998

SECTION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

05-113

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R15W	E1
	T49N R15W	E13 ✓
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

TIME 10:00 A.M.

JAN 8 1999

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Robert L. Jamros, in a field survey on October 18, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E1: P.L.S. - John Burt, DS, 1841. Set post corner of Sections 32 and 33. Fir 6, N.57°E., 27 links. Birch 16, N.65° W., 45 links. * George E. Adair, DS, 1851. W. Pine 14, S.41°E., 21 links, Y. Pine 10, S.30°W., 22 links. ***** Robert E. Schmeling, RLS, 1980. Reported the corner position was restored by R.J. Brotherton, RLS, in 1952 (unrecorded), from the W. Pine 14, S.41°E., 21 links and Y. Pine 10, S.30°W., 22 links. R.J. Brotherton installed a truck axle monument and 8" squared post and witnesses, * W. Pine stump 24", S.42 1/2°E., 65 links, * W. Pine stump 26", N.42°E., 86 links, * N. Pine 14", N.62 1/2°W., 1.96 chains, * N. Pine 17", S.66 1/2°W., 1.36 chains. * Robert E. Schmeling replaced truck axle with a 1" G.I.P. with brass cap. * New bearing trees, W. Pine stump 14", S.74°E., 10.3 feet, (NBT), N. Pine 8", due South, 67.1 feet, (S4 T48N NBT) and attached aluminum locator tag to existing 8" post. * Liber 1, Page 337, Alger County Corner Records. ***** No other corner of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E1: Located corner position by standard field survey and single proportionate measurement. Found monument of the 1980 report and accessories in good condition and in acceptable location. Monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E1: Existing 1" G.I.P. with brass cap. Renewed existing references with BT signs and paint. Set PK nails for measure with aluminum I.D. washers in the following, Existing - White Pine stump 14", S.79°E., 10.98 feet, * Existing - Norway Pine 10", S.04°W., 66.92 feet, * Existing - Red Pine 20", N.58°W., 129.41 feet, * Existing - Red Pine 24", S.73°W., 90.12 feet, * Existing - White Pine stump 24", S.37°E., 56.3 feet, * Existing - White Pine stump 26", N.48°E., 42.8 feet, * Survey marker sign on 6 foot steel post, S.41°E., 1.0 feet. * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date December 16, 1998

