

FEB 23 1999

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 12/16/98

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

05-116

For comers in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R15W	E 1
	T49N R15W	F 13 ✓
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

TIME 10:00 AM

JAN 8 1999

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on October 4, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 comers, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1					●							
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

F1: P.L.S. - John Burt, DS, 1841. Set quarter section post. Beech 20, N.40°E., 48 links. Beech 10, N.22° W., 19 links. \*\*\*\*\* C.C.I. Co. Land Corner Records. Ray J. Brotherton, RLS, 1952. 4" post set straight line between section corners. \* No Gov't BT's found. \* 7" Maple, N.40°E., 15 1/2 links (NBT). \* 18" Y. Birch, S.55°W., 25 links (NBT). \*\*\*\*\* Robert E. Schmeling, RLS, 1980. Recovered point of 4" post, Maple 7", N.40°E., 15 1/2 links (now 9") and Y. Birch 18", S.55°W., 25 links (now stump). \* Replaced post point with 1" G.I.P. with brass cap. \* Made new BT's. \* Beech 17", N.09°E., 17.9 feet (1/4 S33 NBT). \* Red Maple 12", S.14°E., 13.7 feet (1/4 S4 NBT). \* Beech 12", S.48°W., 29.4 feet (1/4 S4 NBT). \* Beech 8", N.66°W., 27.8 feet (1/4 S33 NBT). \* Placed aluminum locator tag on 4" Red Maple 1.5 feet North. \* Liber 1, Page 338, Alger County Corner Records. \*\*\*\*\* No other record of restoration.

B. Description of comer evidence found and/or method applied in restoring or reestablishing comer:

F1: Located comer position by standard field survey and single proportionate measurement. Found monument of the 1980 report and accessories in good condition and in acceptable location. Monument as found is accepted as a careful and faithful reestablishment of the position of the original comer.

C. Description of monument for comer and accessories established to perpetuate locating the position of the comer:

F1: Existing 1" G.I.P. with brass cap. Renewed existing references with BT signs and paint. Set PK nails for measure with aluminum I.D. washers in the following. \* Existing - Beech 22", N.04°E., 18.26 feet. \* Existing - Red Maple 18", S.16°E., 13.93 feet. \* Existing - Beech 20", S.47°W., 29.52 feet. \* Existing - Beech 10", N.67°W., 27.88 feet. \* Existing - twin 5" Red Maple, North, 1.8 feet with aluminum locator tag. \* Survey marker sign on 6 foot steel post, S.38°W., 0.8 feet. \* All bearings are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date December 16, 1998

