SURVEY & REMONUMENTATION

Approved by Alger County
and Survey Remonumentation
Peer Group Under Azt 345 of
A. of 1990 On 1996 1999

FEB 23 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

05-122

REVISED MAY 14,1975 REVISED JAN, 1983 REVISED OCT, 1995

Chairman For corners in	Filing Keq	juirement of ACt 74, Mich. P.A. 3:	
Alger	Located in:	Corner Code #	مسر، و
(County)		į	ME 10:00 A.M.
Public Land Survey Property Controlling in Section	T <u>48N</u> R15W T <u>49N</u> R15W T R T R S T R S T R	H 13	JAN 8 1999 DONALD W. KINNUNEN REGISTER OF DEEDS ALGER COUNTY, MI
3. Miscellaneous Property in Sec.	S TR S TR		Register of Deeds Stamp & File Numbe
5. Private Claims	in a field survey on No.	overniber 11, 19 98 _ do hereby 70, the comer points mentioned in lines 1	A B C D E F G H I J K L 2
and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in		6 -18 - 17 - 16 - 15 - 14 - 13	
conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:		8 - 19 - 20 - 21 - 22 - 23 - 24	
NOTE: Not more than 2 co on this certificate.	mers, all in the same town a	and range, may be recorded	10 30 29 28 27 26 25 11 12 31 32 33 34 35 36
A. Description of original	monument and accessories	s and/or subsequent restoration:	13

Description of comer evidence found and/or method applied in restoring or reestablishing comer:

H1: P.L.S. - John Burt, DS, 1841. Set quarter section post. Beech 5, N.66°E., 25 links.

Hemlock 14, N.36°W., 14 links. **** No other record of restoration.

JAMROS
PROFESSIONAL
SURVEYOR
No.
25349

- H1: Located search area for corner position by standard field survey and single proportionate measurement. Fount squared 6"
 Cedar post, West 10 feet from corner position (author unknown) and blaze lines North -South and East-West. A search was conducted for GLO evidence, it was determined as lost. Monumented corner position as established, midway on line between section corners ½ mile East and West. Established new reference trees. Corner position as monumented is accepted as a careful and faithful reestablishment of the position of the original corner.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- H1: Set Berntsen aluminum monument no. AINB30 with 4" aluminum cap, stamped to identify comer position. Established new reference trees with BT signs, blazed, scribed and painted. Set PK nails for measure with aluminum I.D. washers in the following * Beech 5", N.10°W., 31.12 feet *1/4S BT"; * Beech 5", N.36°E., 29.75 feet, *1/4S BT"; * Beech 6", N.61 ½°E., 6.16 feet, *1/4S BT"; * Beech 5", S.33 ½°W., 14.54 feet, *1/4S BT". * Survey marker sign on 6 foot steel post, N.60°W., 1.5 feet. * All bearings are magnetic.