

**SURVEY &  
REMONUMENTATION**

FEB 23 1999

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 12/16/1998  
Robert L. Jamros  
Chairman

**SECTION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

05-125

For corners in

_____	Alger	Located In:	Corner Code #
_____	(County)		
1. Public Land Survey		T48N R15W	11
		T49N R15W	113 ✓
		T_____ R_____	_____
		T_____ R_____	_____
2. Property Controlling in Section	S_____	T_____ R_____	_____
	S_____	T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____	T_____ R_____	_____
	S_____	T_____ R_____	_____

TIME 10:00 AM

JAN 8 1999

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Robert L. Jamros, in a field survey on November 11, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

11: P.L.S. - John Burt, DS, 1841. Cedar 6" corner of Sections 34 and 35. Spruce 10, N.46°E., 18 links. \* George E. Adair, DS, 1851. Spruce 9, S.48°E., 29 links. Cedar 9, S.21°W., 20 links. \*\*\*\*\* No other record of restoration.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

11: Located search area for corner position by standard field survey and single proportionate measurement between BT corners 1 mile West and 1/2 mile East. Corner position lies in road bed of an old railroad grade crossing a swamp and beaver pond. Found old blaze line running North from corner position. A search was conducted for GLO evidence, it was determined as lost. Monumented proportioned corner position and established reference trees. Corner position as monumented is accepted as a careful and faithful reestablishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

11: Set Berntsen aluminum monument no. AINB30 with 4" aluminum cap, stamped to identify corner position. Established new reference trees with BT signs, blazed, scribed and painted. Set PK nails for measure with aluminum I.D. washers in the following, \* Cedar 6", N.13 1/2°W., 31.66 feet, "S34 BT"; \* Cedar 5", N.47 1/2°E., 21.45 feet, "S35 BT"; \* Cedar 6", S.32°W., 10.61 feet, "S3 BT"; \* Cedar 4", N.78 1/2°E., 14.56 feet, "S35 BT". \* Survey marker sign on 6 foot steel post, N.45°E., 10.0 feet. \* All bearings are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date December 16, 1998

