

**SURVEY &  
REMONUMENTATION**

FEB 19 1998

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 245 of  
P.A. of 1930 On 12-10-1997

Donald W. Carlson  
Chairman

05-93

**SECTION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in \_\_\_\_\_

Located In: \_\_\_\_\_

Corner Code # \_\_\_\_\_

FILED  
TIME 8:30 A.M.

DEC 17 1997

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

1. Public Land Survey	T	<u>49</u>	R	<u>14</u>	<u>A9</u>
	T	<u>49N</u>	R	<u>15W</u>	<u>M9</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	18	17	16	15	14	13	12	11	10	9	8
9												
10	30	29	28	27	26	25						
11												
12	31	30	29	28	27	26	25	24	23	22	21	20
13												

I, Robert L. Jamros, in a field survey on October 09, 1997, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

A9: PLS - William A. Burt, DS, 1841 \* Set post corner of Sections 24 and 25 \* Fir 10, S.42 W., 10 links \* Beech 8, N.65 E., 41 links \*\*\*\* George E. Adair, DS, 1851 \* Beech 7, N.61 W., 43 links \* Sugar 10, S.50 E., 22 links \*\*\*\* R.J. Brotherton, RLS, 1952 \* Set post position from original 5 inch Sugar line tree, 21.35 chains West \* Witnesses - Sugar 16, N.38 E., 45 links \* Hemlock 3, N.51 W., 32 links \* Unrecorded report \*\*\*\* J.R. Radcliffe, RLS, 1963 \* Recovered post and witnesses set by R.J. Brotherton \* Unrecorded Report \*\*\*\* Robert E. Schmeling, RLS, 1980 \* Recovered post point and 2 BT's of R.J. Brotherton, 1952 \* Replaced post point with 1 inch galv. iron pipe w/brass cap and placed 3 inch squared cedar post w/Alum. locator tag \* Witnesses - Red Maple 4, N.57 E., 33.9 feet \* Hard Maple 10, N.4 E., 30.5 feet \* Black Cherry 11, S.35 W., 16.5 feet \* Black Cherry 9, N.09 W., 20.9 feet \* Recorded in Liber 1, Page 325, Alger County corner records. \*\*\*\* No other subsequent restoration.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A9: Found 1 inch galv. iron pipe w/brass cap and 4 inch squared top post w/Alum. locator tag \* Recovered 4 exist. BT's in good condition from 1980 report. \* One adjacent corner one half mile west is on record. \* No other corners of record are within one half or one mile of this corner position. \* R.J. Brotherton, RLS, 1952, established a corner one half mile west, 3.75 chains west of the above mentioned original five inch Sugar Line tree. \* R.J. Brotherton found no evidence of original GLO BT's at this corner one half mile west. \* Paint lines are running in all cardinal directions from this corner. \* There are cabins and camps in the area that have accepted the paint lines and the monument position. \* The existing monument has been accepted and used for surveys in the area. \* Accepted monument position as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A9: Exist. 1 inch galv. iron pipe w/brass cap as stamped to identify the corner position \* Renewed exist. reference trees w/BT signs and paint \* Set PK nails w/Alum. I.D. washers for measure in the following - Exist. BT, Black Cherry 11, S.35 W., 16.58 feet, scribing visible \* Exist. BT, Hemlock 15, N.50 W., 25.36 feet, Double Glazed. \* Exist. BT, Black Cherry 10, S.41 W., 20.91 feet, scribing visible \* Exist. BT, Red Maple 14, N.58 E., 33.83 feet, scribing visible \* All bearings are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date 12/18/1997

