

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T 49 NR 15 W

Alger COUNTY

DESCRIPTION OF CORNER Section Corner common to Sec.'s 17-18-19-20

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

9" Jackpine	S 41° W	44 links
	Marked "S 19 NBT"	
9" Jackpine	N 44° E	38 links
	Marked "S 17 NBT"	
10" Jackpine	S 65° E	68 links
	Marked "S 20 NBT"	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established Section Corner by proportionate measure to Section Corner 1 mile south. 1/4 Corner 1/2 mile east and hemlock line tree 8.48 chs. north.

Placed corner on line between Sec. Cor. south and line tree north.

Distance east to 1/4 Corner checks very good.

No evidence of original spruce pine B.T.s

Placed location poster 13½ chs. north on road.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 5/24/57  
REGISTERED LAND SURVEYOR