

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 NR. 15 W.

Alger

COUNTY

DESCRIPTION OF CORNER Witness Corner to Meander Corner between Sec.'s 17-18 on
shore of Lake Superior

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 13" Red Pine S 13° E 166 links
Marked "W.C. BT"

13" W. Pine S 40° E 169 links
Marked "W.C.BT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

Set witness corner 1 chain south of position of meander corner.

Determined position from original hemlock tree 10.44 chs. south of
meander corner. Tree still green. Chopped out line blaze and determined
age by annual ring count.

No evidence of Meander Corner or B.T.s; believed to have been washed out
by elements.

NOTE: Meander Corner lies 1 ch. north.

Distance along beach to Meander Corner between Sec.'s 18-19 checks very
good with Gov't Recorded Dist. and Bearing.

Placed location poster 4½ chs. south on road.

SURVEYORS SEAL

SIGNED

Billy D. Buckles
REGISTERED LAND SURVEYOR

DATE 5/24/57