

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alger

Form with fields for County, Located In, Corner Code #, and numbered sections 1-5 for survey details.

Register of Deeds Stamp & File Number

Jul 07 2000

I, Stephan J. Szyszkoski, in a field survey on 19, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13, containing numbers 1-36 and two black dots at row 9, columns C and D.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(89) Quarter corner common to Sections 19-30. Corner re-monumented in the original position in 1957 by Billy D. Buckler, RLS. 1" pipe with 4" brass cap. 13" W.Pine N65W 84 links, 11" Red Pine N27E 54 links.
(C9) Corner common to Sections 19-20-29-30. Corner re-monumented in the original position in 1956 by Billy D. Buckler. 1" pipe with 4" brass cap. 6" Red Pine N32E 92 links, 8" Red Oak S38E 17 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(89) Recovered the 1957 monument, in good condition, at record bearing and distance from the 1957 NBTs: The Red Pine is in good condition and the White Pine is a cut stump. Left the monument in place and marked new witnesses as described below. An E-W trail is 15' north of the monument.
(C9) Recovered the 1956 monument at record bearing and distance from the record R.Pine NBT, in good condition, and the Oak NBT, now a cut stump. Found no evidence of the original BT noted in the 1956 record. Left the monument in place and made new witnesses as described below. An E-W trail is 16' north of the monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(89) Found 1" pipe with 4" brass cap. Blazed, scribed, and set measuring nails in the following: 20" R.Pine N30E 33.75' "1/4S NBT", 6" W. Birch N68W 52.05' do, 5" R. Pine N50W 39.45' do, 5" R. Pine East 50.95' do. Bearings are magnetic. Distances are to nail with tag.
(C9) Found 1" pipe with 4" brass cap. Blazed, scribed, and set measuring nails in the following: 16" R.Pine N35E 60.45' "S20" (1956 NBT), 6" W.Pine N26W 8.4' "S19", 8" J.Pine N78W 7.25' "S19", 10" W.Pine S28E 32.3' "S29". Bearings are magnetic. Distances to nail with tag.



Signed by Stephan J. Szyszkoski, 33986, Date 1/10/01, Surveyor's Michigan License No.