

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Alger  
(County)

Located In: Corner Code ≠#

- |                                    |                           |           |
|------------------------------------|---------------------------|-----------|
| 1. Public Land Survey              | T <u>49N</u> R <u>15W</u> | <u>C8</u> |
|                                    | T _____ R _____           | _____     |
|                                    | T _____ R _____           | _____     |
|                                    | T _____ R _____           | _____     |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____     |
|                                    | S _____ T _____ R _____   | _____     |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____     |
|                                    | S _____ T _____ R _____   | _____     |

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jul 07 2000

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(C8) Quarter corner common to Sections 19-20. Corner reestablished by single proportionate measurement to the original record by Billy D. Buckler RLS in 1957. 1" pipe with 4" brass cap. 9" Jack Pine N45W 6 links, 11" Jack Pine S82E 15.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C8) Recovered the 1957 monument, in good condition, at record bearing and distance from the 1957 accessories: The Jack Pine NW is standing but dead, the Jack Pine SE is a cut stump. Verified position of the monument with respect to section corners 1/2 mile north and south. Left the monument in place and marked new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C8) Found 1" pipe with 4" brass cap.  
 Blazed, scribed, and set measuring nails in the following:  
 6" J. Pine N12E 18.2' "1/4S NBT"  
 12" J. Pine N48W 8.3' do  
 6" J. Pine N72W 15.35' do  
 14" J. Pine S31W 19.95' do  
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski Date 1/10/01  
 Surveyor's Michigan License No. 33986