

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 N NR. 15 W.

Alger

COUNTY

DESCRIPTION OF CORNER Section Corner common to Sec.'s 21-22-27-28

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 15" Red Pine N 31° E 102½ links
Marked "S 22 NBT"
11" W. Pine S 69° E 40 links
Marked "S 27 NBT"
14" Red Pine S 70° W 125 links
Marked "S 28 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established Section Corner by preportionate measure:
East 6.54 chs. to line tree.
West 10.57 chs. to line tree.
North 40.06 chs to good 1/4 corner.

No evidence of original Corner.

SURVEYORS SEAL

SIGNED

REGISTERED LAND SURVEYOR

DATE 5/23/57