

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 NR. 15 W.

Alger

COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sec.'s 21-22

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 10" Red Pine S 27° E 57 links

Marked "1/4 S NBT"

7" W. Pine S 81° W 76 links

Marked "1/4 S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced from two original B.T.s. One hemlock bearing S 66° W 27 links, poor condition. Notch and overgrowth remains. One yellow pine bearing N 57° E 26 links. Stub burned, notch and trace of face remains. No evidence of use.

1/4 corner lies 44 links west of 40.00 ch. marker from north.

SURVEYORS SEAL

SIGNED

Silly D. Buckles
REGISTERED LAND SURVEYOR

DATE 5/23/52