

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49. NR. 15. W.

Alger COUNTY

DESCRIPTION OF CORNER Meander Corner between Sec.'s 18-19 on shore of Lake Superior

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 11" Red Pine S 13° W 126 links
Marked "M.C. NBT"
10" W. Pine S 42° E 92 links
Marked "M.C. NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established meander corner by extending line of old blazes found along Section line between Sec.'s 18-19. A proportionate distance. Position checks with shore line.

Bank has washed badly. No evidence of B.T.s. B.T.s believed to have been washed away by elements.

SURVEYORS SEAL

SIGNED Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 5/23/57