

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 .. NR. 15 W ..

Alger COUNTY

DESCRIPTION OF CORNER Section Corner common to Sec.'s 28-29-32-33

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

<u>12" W. Pine</u>	<u>S 77° W</u>	<u>56 links</u>
	<u>"S 32 NBT"</u>	
<u>12" Red Pine</u>	<u>N 80° E</u>	<u>67 links</u>
	<u>"S 28 NBT"</u>	
<u>9" W. Pine</u>	<u>N 32° W</u>	<u>37 links</u>
	<u>"S 29 NBT"</u>	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Corner from one white pine B.T. bearing N 44° E 28 links, tree down and in poor condition. Line of old blazes south from Corner. Found evidence of stake in soil.

Placed location pester 6.00 chs. north on road.

SURVEYORS SEAL

SIGNED

Billy D. Buckles
REGISTERED LAND SURVEYOR

DATE 6/4/57