

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 .. NR. 15 W ..

Alger .. COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 27-28-33-34

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER	14" Red Pine	N 4° W	52 links
		"S 27° NBT"	
	12" Red Pine	N 56° E	72 links
	m	"S 28° NBT"	
	8" W. Pine	S 68° W	30 links
		"S 33° NBT"	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established corner by double proportionate measure from corners:

$\frac{1}{2}$ mile south
 $\frac{1}{2}$ mile east
1 mile north
1 mile west

Placed location poster on road 8.00 chs. west of corner.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 11/5/57
REGISTERED LAND SURVEYOR