

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 .. NR. 15 W ..

Alger

COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sec.'s 27-34

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER	<u>10" Hemlock</u>	<u>S 31° E</u>	<u>60 links</u>
		<u>"1/4 S NBT"</u>	
	<u>5" Soft Maple</u>	<u>S 57° W</u>	<u>26 links</u>
		<u>"1/4 S NBT"</u>	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 corner at old scribed stake set by unknown persons.

Found hemlock stump bottom in proper position for original B.T.

Scribed post found by Forestry Division Survey Crew.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 11/5/57
REGISTERED LAND SURVEYOR