

JAN 18 2001

Approved by Alger County Land Survey Remonumentation Peer Group Under Act 345 of P.A. of 1980 On 12-13-2000

*Donald W. Kinnunen*  
Chairman

05-204

SECTION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 15W	A01
	T 49N R 15W	A13 ✓
	T 48N R 16W	M01
	T 49N R 16W	M13
2. Property Controlling in Section	S ___ T ___ R ___	___
3. Miscellaneous Property in Section	S ___ T ___ R ___	___

FILED  
TIME 8:50 Am.  
DEC 20 2000  
DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Robert L. Jamros, in a field survey on May 12, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
A01: PLS John Burt, DS, 1841. Set post corner of Township 48 and 49 North between Ranges 15 and 16 West. Y. Pine 14", N.26°E., 67 links. Spruce 9", S.27°W., 14 links. \*\*\*\*\* C.C.I. Co. Ray J. Brotherton, RLS, 1948. Set iron and 4" post from Government BT, a Y. Pine stump, N.26°E., 67 links, notch plain. W. Pine 6", S.48°E., 62.5 links. W. Pine 10", N.56°W., 97.5 links. Unrecorded.\*\*\*\*\* Michigan Department of Conservation, Forestry Division. Billy D. Buckler, RLS, 1960. Set 1" iron pipe with 4" brass cap at corner position of a broken spring leaf iron. Found Y. Pine stump bearing Northeast from corner position, notch and part of bottom blaze plain. W. Pine 10", (S6 NBT) S.43°E., 63 links. R. Pine 14" (S36 NBT) N.08°E., 126 links. Liber 2, Page 159, Alger County corner records. \*\*\*\*\* No other subsequent restoration of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
A01: Found 1" iron pipe with 4" brass cap and NBT's of the 1960 report in good condition. Found broken spring leaf iron at base of above monument, NBT's of 1948 report are lost. Corner monument position as found is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
A01: Existing 1" iron pipe with 4" brass cap as found. Renewed existing NBT's with BT signs and paint. Established additional reference trees with BT signs, blazed, scribed and painted. Set PK nails for measure with aluminum I.D. washers in the following: Ex. NBT, R. Pine 26", N.01°W., 83.63 feet (blaze scars); Ex. NBT, W. Pine 28", S.43°E., 41.76 feet (blaze scars); R. Pine 8", S.54°W., 33.64 feet (S1 BT); R. Pine 14", N.58°W., 30.0 feet (S36 BT). Survey marker sign on 6 foot steel post, S.34°W., 1.0 feet. All bearings are magnetic.

Signed by *Robert L. Jamros*  
Surveyor's Michigan License No. 25849

Date Dec. 17, 2000

