

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49. NR 15 W. . .

Alger

COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 20-21-28-29

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER	<u>14" Red Pine</u>	<u>N 22° E</u>	<u>36½ links</u>
		<u>"S 21 NBT"</u>	
	<u>10" Red Pine</u>	<u>N 15° W</u>	<u>62 links</u>
		<u>"S 20 NBT"</u>	
	<u>13" Hemlock</u>	<u>S 2° W</u>	<u>47½ links</u>
		<u>"S 29 NBT"</u>	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced section corner from two hemlock B.T.s bearing N 49° W 14 links and S 36° E 31 links. Both stumps down and shattered but scribe marks very plain on wood fragments.

Corner found while checking lines run by Survey Crew.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 11/6/57
REGISTERED LAND SURVEYOR