

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 NR. 15 W.

Alger COUNTY

DESCRIPTION OF CORNER 1/4 corner for sections 20 and 21.

DESCRIPTION OF CORNER MONUMENT 1" pine with 4" brass cap.

WITNESSES TO CORNER 5-2-58

7" jack pine N 80°, E 9 links. Marked "1/4SNEBT"

6" jack pine S 80°, W 18 links. Marked "1/4SNEBT"

Squared and scribed 7" jack pine 4 links S.E. of corner.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED. Replaced from one W. pine stump (probably clearing tree), bearing N 20°,
W 18 links. Found traces of stake in soil. Found possible site of yellow pine
stump bearing S 62°, E 33 links. Position checks with original section corners
1/2 mile north and south.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 6-17-59
REGISTERED LAND SURVEYOR