

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49. NR. 15. W

----- A l g e r ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 14, 15, 22, and 23

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 9" Hard Maple (S 15 NBT) North 33 Links

8" Hard Maple (S 14 NBT) N 82° E 10 Links

8" Soft Maple (S 23 NBT) S 20° E 25 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed at old wood post set by unknown surveyor. Possibly Cleveland Cliffs Iron Company mens. Found no evidence of original corner. Many old blases in vicinity. Position fits with corners in this area.

Corner was placed and witnessed June 17, 1960 with Russell Hinds.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 7/27/60
REGISTERED LAND SURVEYOR
Billy D. Buckler