

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49. NR. 15. W.

A l g e r COUNTY

DESCRIPTION OF CORNER Witness corner to Meander corner between Sections
17 and 18 on Shore of Lake Superior.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 17" Red Pine (BT) S 34° E . . . 57 1/2 Links

8" Red Pine (BT) S 48° W . . . 108 1/2 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

Set witness corner in new position 2.00 chains south of witness corner set
5/24/58. Former Corner removed by ice action.

Corner was placed and witnessed 7/8/59.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 3/20/61
REGISTERED LAND SURVEYOR
Billy D. Buckler