

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>20</u> T <u>49N</u> R <u>15W</u>	<u>4</u>
	S <u>20</u> T <u>49N</u> R <u>15W</u>	<u>5</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on 05/11/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(4-Sec. 20) Northwest 1/16 corner, Section 20. Not established in the original survey.

(5-Sec. 20) North 1/16 corner, Section 20. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(4-Sec. 20) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

(5-Sec. 20) Established the corner midway and on a straight line between Quarter corner D7 1318.38' north and the intersection of 1/4 lines of Section 20 1318.38' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

NW 1/16, Section 20

North 1/16, Section 20

(4) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 9" J.Pine N69W 6.35' mrkd "NW1/16 BT"
 6" J.Pine N31E 16.5' do
 6" J.Pine S79E 9.9' do
 8" J.Pine S35W 20.9' do
 Bearings are magnetic.

(5) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 7" J.Pine N63W 85.3' mrkd "N1/16 BT"
 11" R.Pine S51E 55.35' do
 14" R.Pine S44W 126.0' do
 4" Maple N47E 82.85' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 05/18/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division

