

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Alger</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 19 T 49N R 15W	C-S-S 1/64
	S 19 T 49N R 15W	SW-SE 1/64
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on 05/12/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(C-S-S 1/64) The NE corner of the S1/2 of the SE1/4 of the SW1/4 of Section 19. Not established in the original survey.

(SW-SE 1/64) The Center of the SW1/4 of the SE1/4, Section 19. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(C-S-S 1/64) Established the corner midway and on a straight line between Quarter corner B9 660.81' south and 1/16 corner #12 660.81' north.

(SW-SE 1/64) Established the corner at the intersection of straight lines connecting opposite 1/64 corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

<u>C-S-S 1/64</u>	<u>SW-SE 1/64</u>
Set 1"IDx36" I.pipe w/4" alum MDNR cap.	Set 1"IDx36" I.pipe w/4" alum. MDNR cap
Set measuring nail with MDNR tag in the side of:	Set measuring nail with MDNR tag in the side of:
12" R.Pine S40W 16.25' mrkd "1/64 BT"	8" W.Pine North 10.0' mrkd "1/64 BT"
10" R.Pine N71W 18.6' do	10" R.Pine S42E 12.7' do
7" W.Pine S71E 29.25' do	9" R.Pine S12W 15.45' do
13" R.Pine N03E 4.05' do	11" R.Pine N86W 13.7' do
Bearings are magnetic.	Bearings are magnetic.

Signed by Stephan J. Szyszkoski Date 05/18/2010  
 Surveyor's Michigan License No. 33986



For the Michigan Department of Natural Resources and Environment, Forest Management Division